



Playground Specialists Inc
 29 Apples Church Road
 Thurmont, MD 21788
 +1 8003850075
 www.playspec.com

ADDRESS

CITY OF HYATTSVILLE
 ATTN: LESLEY RIDDLE
 4633 ARUNDEL PLACE
 HYATTSVILLE, MD 20781

SHIP TO

THE SPOT
 C/O PLAYGROUND
 SPECIALISTS

Proposal 31982A

DATE 07/03/2024

SALES REP

DAVE SMITH

TYPE	QTY	RATE	AMOUNT
NOTE HGAC CONTRACT #PR11-20			
BERLINER PLAY EQUIPMENT O'TANNENBAUM 3.1	1	15,768.00	15,768.00
BERLINER PLAY EQUIPMENT TERRANO.196 (HAMMOCK W/ BALLS)	1	8,112.00	8,112.00
DISCOUNT HGAC CONTRACT 6% DISCOUNT OFF BERLINER LIST PRICE ABOVE	1	-1,432.80	-1,432.80
PERCUSSION PLAY SOPRANO QUARTET ENSEMBLE - INGROUND	1	7,820.00	7,820.00
F-124 PLAYSPEC CUSTOM WELCOME SIGN	1	842.00	842.00
INSTALLATION CERTIFIED INSTALLATION OF ALL EQUIPMENT ABOVE INCLUDING LIFETIME INSTALLATION WARRANTY - INCLUDES FREIGHT AND DESIGN CHARGES	1	34,780.80	34,780.80
RCP SHELTERS TS-BS-SS2634-02-TG - 26' X 34'-6" STEEL SINGLE SLOPE BAND SHELL W/ T&G WOOD ROOF DECK & METAL ROOFING - INCLUDES PLATE STEEL TEMPLATES, HDG ANCHOR BOLTS: F1554-36 W/ WASHER & NUTS, MD CERT DRAWINGS WITH STANDARD RCP FOUNDATION DESIGN, POWDER COATED TUBE STEEL, 26 GA EXPOSED FASTENER MAX-RIB METAL ROOFING, #1 GRADE 2X8 T&G SOUTHERN YELLOW PINE ROOF DECK, 7' 6" EAVE HEIGHT, AND FREIGHT	1	63,000.00	63,000.00

TYPE	QTY	RATE	AMOUNT
RCP SHELTERS TS-SQ32-04-TG - 32' X 32' STEEL SQUARE HIP SHELTER W/ T&G WOOD ROOF DECK & METAL ROOFING - INCLUDES PLATE STEEL TEMPLATES, HDG ANCHOR BOLTS: F1554-36 W/ WASHER & NUTS, MD CERT DRAWINGS WITH STANDARD RCP FOUNDATION DESIGN, POWDER COATED TUBE STEEL, 26 GA EXPOSED FASTENER MAX-RIB METAL ROOFING, #1 GRADE 2X8 T&G SOUTHERN YELLOW PINE ROOF DECK, 7' 6" EAVE HEIGHT, AND FREIGHT	1	68,507.00	68,507.00
INSTALLATION COMPLETE AND CERTIFIED INSTALLATION OF SHELTERS ABOVE AS SUPPLIED BY MANUFACTURER	1	52,603.00	52,603.00
NOTE ALL AREAS TO BE GRADED BY OTHERS AND READY FOR NEW EQUIPMENT, SURFACING, SHELTERS, AND CONCRETE PRIOR TO INSTALLATION			
NOTE CONTRACTOR NOT RESPONSIBLE FOR SECURITY AND VANDALISM DURING RUBBER AND CONCRETE INSTALLATION AND CURING TIME			
NOTE CONCRETE FOOTINGS FOR RCP PRODUCTS, CONCRETE PADS PLUS STONE AGGREGATE NOT INCLUDED AND TO BE DONE BY OTHERS			
NOTE SAFETY SURFACING, TIMBERS, AND DRAINAGE NOT INCLUDED IN PRICING ABOVE			
*Net 30 w/ PO		SUBTOTAL	250,000.00
*3% service charge for all credit card payments.		TAX (0%)	0.00
*Pricing only guaranteed for 30 days unless specified above.			
*Absolutely no engineering, permits, permit fees, wage rates, bonding, or additional insurance included in above pricing unless specified on line item.			
*Additional mobilization, poor soils, limited access, or utility issues may result in change orders.			
*Standard lead times always apply. Contact sales agent for details.			
**Sign and return when approved. Thank you!			
TOTAL			\$250,000.00

Accepted By

Accepted Date