



913 Ridgebrook Road | Suite 302 | Sparks, MD 21152
P: 410.785.0875 | www.mdswm.com | info@mdswm.com

TASK ORDER PROPOSAL

Date: January 18, 2024

To: City of Hyattsville
Lesley Riddle: lriddle@hyattsville.org
Hal Metzler: hmetzler@hyattsville.org
Priyanka Joshi: pjoshi@hyattsville.org

Project: **Task Order #37**
King Park Landscaping
SWM Project 20008MN37 - TO37

In accordance with your request, Stormwater Maintenance, LLC (dba SMC) is pleased to submit this Task Order proposal for the requested landscape and maintenance work at the above referenced site. This proposal is based on the design plans provided by Low Impact Development Center, dated 12/21/2023, your request, and our understanding of the project at this time.

Scope of Services:

To this end, SMC proposes to perform work as specifically described in the following scope of work:

1. Mobilize a construction crew and all necessary equipment, one time, to the site.
2. This proposal assumes unobstructed access will be available for the crew to complete required work. Obstructed access and delays to the proposed work plan may result in additional charges. Traffic control materials (signs, cones, drums) and setup will be handled by SMC.
3. Furnish and install approximately (1,700) SF of proposed paver pathway per Detail D.1 on Sheet C-1.05. In the event the Belgard Dublin Cobble Paver in Sable Blend, Pattern B (specified) is unavailable, an equivalent paver will be selected and approved by the City.
 - a. Includes 1" C-33 sand for paver bedding.
 - b. Includes 3" aggregate base for paver bedding.
 - c. Includes 3" wet concrete edge restraint.
 - d. Includes removal and disposal of existing pavers.
 - e. Includes subgrade removal.
4. Furnish and install up to (175) SF of assorted flagstones for Stepper Pathway.
5. Remove and dispose of (55) LF of existing Timber Wall.
6. Furnish and install approximately (150) LF of Timber Wall with Low Ornamental Fence at NE Planting Bed per Details J-1 & J-2 on Sheet C-1.05.
7. Furnish and install approximately (64) LF Low Ornamental Fence on Existing Wall at NW Planting Bed.
8. Furnish and install (2) Bollards with Chain per Details C.1 & C.2 on Sheet C-1.05.
9. Install (1) Stroller Sign & (1) Way-Finding Sign per Detail F.1 on Sheet C-1.05
10. Remove and dispose of (7) crepe myrtle trees and (8) nandina domestica shrubs.
11. Furnish and install up to (120) CY of topsoil within planting beds and plan-specified areas as noted on Sheet C-1.03.
12. Furnish and install up to (555) SY of sod for drainage as noted on Sheet C-1.03.

We protect and restore watersheds.
www.MdSWM.com

- 13. Furnish and install landscape plants as shown and tabulated on Sheets L-1.00 - L-1.03.
 - a. Includes one year warranty with a one-time replacement at the end of the warranty period.
 - b. SMC will not be responsible for the death or damage of plants due to wildlife predation or vandalism.
- 14. Stabilize all disturbed areas with seed and straw mulch or matting
- 15. Provide photographic documentation in SMC's format that confirms work has been completed.

Work proposed herein is limited to what is described in the above Scope of Services. Any work requested to be performed, is subsequently requested by the Client, or otherwise not described above may result in additional costs. You will be advised of any additional costs prior to commencing additional work.

Terms: Per existing contract dated January 7, 2020

Cost: \$202,475.00 Lump Sum

Submitted by:



Tyler Gardner, PE
Project Manager

Client Acceptance:

Your authorization for SMC to proceed with the work via written, verbal, email, fax, purchase order, or other preferred contract format acknowledges your acceptance of this Authorization and the terms and conditions of our existing contract.

Agreed and Accepted this _____ day of _____, 2024.

By _____

Printed Name: _____

Title: _____

By signing above, you acknowledge that you are authorized to enter into contractual agreements for the entity that is responsible for the work proposed herein.