Estimate

www.liftnow.com
sales@liftnow.com - Fax: 914-734-7479
1-800-LIFTNOW

Date:	3/5/2021
Valid Until	4/4/2021
Quote #:	HyattsvileAirandLube
Sales Rep	Paul

Customer:

City of Hyattsville
4633 Arundel Place
Hyattsville MD 20781
Attn: Hal Metzler
Deputy Director of Public Works

Sourcewell Member ID: 33637

Qty	Description	List Price	Sourcewell Price
1	Air system- Install air compressor, air tank and air dryer with bypass Install 2 - 1/2" air reels in center of shop, 4 - 3/8" 2 in front and rear of shop with shut off valves. Install 360' 1" L copper loop around shop. Install 280' 1/2" L copper air drop in shop, 6 air drops between shop door, 3 air drops on back wall of shop, 1 air drop to tire changer, 2 air drops on 2 heavy duty lifts with 3 air regulators, 2 air drops on 2 twin post lifts with air regulator Air drops on heavy duty lifts will be installed on stands that needs to be fabricated out of strut. Install 1/2" air line to tank room, 4 drops all pumps will have shut off valves.	$17,940.00	**$14,940.00**
1	Lubrication System Install 220' 5/8" seamless tubing (049 wall) Install 4 oil reels and meter, 2 banks of 2 reels Install 4 oil pumps on wall in tank room with 55 gal drum. Drop tubes & strut need to be installed from floor to ceiling, (Drywall) All copper piping and fitting, seamless tubing and fitting, hose, ball valves, & air coupler will be supplied. Hotel/travel costs, high reach lift and forklift rentals included in cost.	$38,880.00	**$29,880.00**

Special Notes and Instructions

PLEASE ADD SALES TAX. ELECTRICAL HOOK-UP, AIR HOOK-UP, REMOVAL OF EXISTING EQUIPMENT AND ANY CONCRETE WORK, IF NECESSARY, IS THE RESPONSIBILITY OF THE CUSTOMER. (UNLESS OTHERWISE SPECIFIED ABOVE). CUSTOMER IS ALSO RESPONSIBLE FOR THE PRESENCE OF ANY AND ALL SUB-SURFACE FEATURES OR CONDITIONS INCLUDING BUT NOT LIMITED TO ROCK, LEDGE, GROUND WATER, CONCRETE OF GREATER THAN 6" THICKNESS, AIR, UTILITY OR RADIANT HEATING LINES WHICH MAY REQUIRE RELOCATION OR REPAIR. REMOVAL OR DISPOSAL OF ANY CONTAMINATED SOIL, IF PRESENT, IS THE RESPONSIBILITY OF THE OWNER OF THE PROPERTY. ANY PERMITS, FILINGS OR FEES ARE THE RESPONSIBILITY OF THE CUSTOMER. CUSTOMER IS RESPONSIBLE FOR HAVING A FORKLIFT TO UNLOAD AND RECEIVE THE SHIPMENT. PRICES ARE GOOD FOR 30 DAYS. ADD 4% IF USING CREDIT CARD. MUST SIGN CHARGEBACK AGREEMENT AND AUTHORIZATION.

Sourcewell
Awarded Contract
Contract # 013020-LFT

Subtotal	$56,820.00
Discount	**$12,000.00**
Freight	INCLUDED
Total	$44,820.00

Above information is not an invoice and only an estimate of services/goods described above.

Please confirm your acceptance of this quote by signing this document.

Signature _____
Print _____
Date _____