



913 Ridgebrook Road | Suite 302 | Sparks, MD 21152
P: 410.785.0875 | www.mdswm.com | info@mdswm.com

TASK ORDER PROPOSAL

Date: August 15, 2023

To: City of Hyattsville
Hal Metzler: hmetzler@hyattsville.org

Project: **Task Order #028**
Drainage Swale Cleanout - 6101 43rd Street
SMC Project 20008MN28

In accordance with your request, Stormwater Maintenance, LLC (dba SMC) is pleased to submit this Task Order proposal for the requested repair work at the above referenced site. This proposal is based on our observations made during our initial site meeting with you, site information provided by you, and our understanding of the project at this time.

Generally, it is SMC's understanding that the City of Hyattsville (City) requests our team to repair a drainage swale at 6101 43rd Street. Stormwater flowing through a modified curb cut has caused sediment accumulation in the receiving swale, restricting flow to the drain and causing flooding in the adjacent properties.

The purpose of this task order is to remove the drainage restriction and mitigate the flooding of adjacent properties.

Scope of Services:

SMC proposes to perform work as specifically described in the following scope of work one time:

1. Mobilize a maintenance crew to the site. SMC will access the swale from 44th Avenue, between 6100 and 6022. This proposal assumes that traffic control (barricaded parking spaces and drive lanes where needed) will be handled by City personnel at the request of SMC and unobstructed access will be available for the crew to complete their required work. Obstructed access and delays to the proposed work plan may result in additional charges.
2. Remove and dispose of overgrown vegetation, chain link fence, and accumulated sediment within the drainage swale. Fence will not be replaced.
3. Remove and dispose of approximately (10) LF of curb and gutter to mitigate swale flow restriction.
4. Furnish and install up to (20) tons of class 1 riprap at the end of the driveway apron to dissipate velocity and widen the stormwater flow path from the driveway apron to the swale and inlet.
5. Stabilize all disturbed areas with soil stabilization matting and temporary seed.
6. Provide a work completion report documenting the repair.

Work proposed herein is limited to what is described in the above Scope of Services. Any work requested to be performed, is subsequently requested by the Client, or otherwise not described above may result in additional costs. You will be advised of any additional costs prior to commencing additional work.

We protect and restore watersheds.
www.MdSWM.com

Terms: Per existing contract dated January 7, 2020.

Cost: \$19,650.50 (Lump Sum)

Submitted by:



Justin Seigel
Director of Construction

Client Acceptance:

Your authorization for SMC to proceed with the work via written, verbal, email, fax, purchase order, or other preferred contract format acknowledges your acceptance of this Authorization and the terms and conditions of our existing contract.

Agreed and Accepted this _____ day of _____ 2023

By: _____

Printed Name: _____

Title: _____

By signing above, you acknowledge that you are authorized to enter into contractual agreements for the entity that is responsible for the work proposed herein.